| No. | Item of work | Unit | Rate | Quantity | Rate to be quoted in | |
|---|---|---|---|---|---|---|
| | | | | | Figures | Words |
| 3 | Turfing the slopes of the bund and watering till it is satisfactory .. .. .. | S.yd. | 0 0 10 | 673 | | |
| 4 | Earthwork excavation and putting jack bund for deviating the halla, including lead and lift, watering and tamping, etc., complete .. .. .. .. | C.yd. | 0 3 6 | 222 | | |
| 5 | Turfing the slopes of the jack bund and watering till it is satisfactory .. | S.yd. | 0 0 10 | 200 | | |
| | *Sluice.* | | | | | |
| 1 | Earthwork cut opening the bund and refilling the same with watering and tamping .. | C.yd. | 0 5 0 | 200 | | |
| 2 | Earthwork excavating for foundation and using the spoil to the bund with lead and lift, etc. .. .. .. .. | C.yd. | 0 3 0 | 100 | | |
| 3 | Burnt stone jelly concrete in surki mortar .. | C.ft. | 0 4 0 | 75 | | |
| 4 | Burnt brick in surki mortar .. .. | „ | 0 4 6 | 100 | | |
| 5 | Burnt stone slabs 6″ thick exposed surfaces one line dressed and fixed in surki mortar | S.ft. | 0 4 6 | 50 | | |
| 6 | Plastering with surki mortar .. .. | Sqr. | 3 8 0 | 3·00 | | |
| 7 | Rough stone work with the required lead, jelly backing and jelly wedging, etc. .. | C.yd. | 1 2 0 | 50 | | |
| 8 | Cutting holes in the slabs .. .. | Each | 0 10 0 | 2 | | |
| 9 | Providing plug and rod with locking arrangement .. .. .. | „ | 14 0 0 | 1 | | |

N. LAKSHMINARASIMHAIYA,
*Executive Engineer.*

## KOLAR DIVISION.

*Abstract Notification dated 20th June 1940.*

The attention of the public is invited to the detailed notification dated 19th June 1940, published on pages 1528-1531, Part VI of the *Mysore Gazette*, dated 27th June 1940, regarding tenders for opening a Feeder Channel to the Kadalveni Tank (Register No. 32), from Kumadvathi River in Goribidnur Taluk.

The last date for lodging of tender is up to 2 P.M. on 13th July 1940.

---

*Abstract Notification dated 24th June 1940.*

The attention of the public is invited to the detailed notification dated 23rd June 1940, published on pages 1532-1534, Part VI of the *Mysore Gazette*, dated 27th June 1940, regarding tenders for restoring Chatrakodalli Chikkere (unrestored breached minor tank) Register No. 13/784 of Kolar Taluk. The last date for lodging of tender is up to 2 P.M. on 13th July 1940.

---

*Notification dated 28th June 1940.*

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 22nd July 1940, for restoring Ramachandrapura Jadayyanakere Tank, Reg. No. 648 (unrestored minor Tank) of Mulbagal Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Restoring Ramachandrapura Jadayyanakere Tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 200 paid to the credit of "17 (a) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 22nd July 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same when lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

*Note.*—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

*Note.*—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

*N.B.*—Copies of tenders in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of Re. 0-4-0 per form.

Abstract estimate for restoring Ramachandrapura Jadayyanakere Tank, Registered No. 648 of Mulbagal Taluk (unrestored minor tank).

| No. | Items of work | Unit | Rate | Quantity | Rates to be tendered |
|---|---|---|---|---|---|
| | (*Bund at R.L.* 56·00). | | Rs. a. p. | | |
| 1 | Clearing thick jungle with roots .. .. | Grade | 2 0 0 | 12 | |
| 2 | Removing ant-hills and filling with sand .. | Each | 1 0 0 | 10 | |
| 3 | Earthwork excavation cutting grips and trenches for the seat of new earthwork .. .. | Grade | 2 0 0 | 12 | |
| 4 | Earthwork to bund and using the same with watering and tamping, including lead and lift, etc., complete .. .. .. .. | C.yd. | 0 3 0 | 4,703 | |
| 5 | Turfing to slopes of bund .. .. .. | S.yd. | 0 0 9 | 3,616 | |
| 6 | Constructing old stone revetment work with new jelly wedging, etc., complete .. .. | C.yd. | 0 8 0 | 284 | |
| 7 | Constructing new stone revetment with jelly backing and wedging, etc., complete .. .. | ,, | 1 8 0 | 1,039 | |
| 8 | Providing and fixing new grade stones with figuring and painting, etc., complete .. .. | Each | 1 8 0 | 19 | |
| 9 | Do Index stones do .. | ,, | 0 6 0 | 19 | |
| 10 | Do Regd. No. stones do .. | ,, | 3 0 0 | 1 | |
| 11 | Do B.M. stones do .. | ,, | 2 8 0 | 2 | |
| | Total Rupees .. | | | | |
| | II. *Constructing a new C.I. pipe sluice at C.S.* 8 *with cill at* 44·00. | | | | |
| 1 | Earthwork cutting open the bund and refilling with watering and consolidation, etc. .. .. | C.yd. | 0 5 0 | 78 | |
| 2 | Burnt stone jelly concrete in surki mortar .. | C.ft. | 0 4 0 | 108 | |
| 3 | Size stone in surki mortar .. .. .. | ,, | 0 4 6 | 431 | |
| 4 | Burnt stone slabs 6″ thick, dressed and fixed in surki mortar .. .. .. .. | S.ft. | 0 4 6 | 51 | |
| 5 | Drilling holes in orifice and gibbet slabs .. .. | Each | 0 8 0 | 3 | |
| 6 | Cement pointing after raking joints (1 : 3) .. | Sqr. | 3 8 0 | 1·66 | |
| 7 | Providing C.I. pipes of 6″ dia. including Railway freight, carting charges and fixing, etc., complete .. .. .. .. .. | R.ft. | 3 0 0 | 42 | |
| 8 | Providing and fixing new plug and rod with locking arrangement, etc., complete .. .. | Each | 15 0 0 | 1 | |
| | Total Rupees .. | | | | |

| No. | Items of work | Unit | Rate | Quantity | Rate to be tendered |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | |
| | *III. Constructing a masonry Waste Weir at R.L. 51·00—120 ft. long.* | | | | |
| 1 | Earthwork excavation foundation using the earth to bund with watering and consolidation, etc. | C.yd. | 0 3 0 | 355 | |
| 2 | Burnt stone jelly concrete in surki mortar .. | C.ft. | 0 4 0 | 350 | |
| 3 | Burnt size stone in surki mortar .. .. | ,, | 0 4 6 | 652 | |
| 4 | Burnt stone slab 6" thick, dressed and fixed in surki mortar .. .. .. .. | S.ft. | 0 4 6 | 215 | |
| 5 | Cement pointing after raking joints (1 : 3) .. | Sqr. | 3 8 0 | 6·00 | |
| 6 | Providing joggle joints .. .. .. | Each | 0 8 0 | 20 | |
| 7 | Constructing rough stone apron and wings .. | C.yd. | 1 8 0 | 80 | |
| | Total Rupees .. | | | | .. |

C. R. IYENGAR,
*Executive Engineer.*

## MANDYA DIVISION.

*Abstract Notification dated 22nd June* 1940.

The attention of the public is hereby invited to the notification on pages 1557-1559, Part VI of the issue of the *Mysore Gazette*, dated 27th June 1940, inviting tenders for increasing the capacity of Chennegowdanakere of Kadaballi Village, Nagamangala Taluk.

The last date fixed for the receipt of tender in this office is 3 P.M. on the 15th July 1940.

B. S. NARASINGA RAO,
*Executive Engineer.*

## SHIMOGA DIVISION.

*Abstract Notification dated 13th June* 1940.

The attention of the public is drawn to the notification calling for tenders for constructing flushing latrine in the compound of the District Offices, Shimoga, published on pages 1476-1478, Part VI of the *Mysore Gazette*, dated 20th June 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on 6th of July 1940.

Earnest money required for the work is Rs. 80 which should be credited to the Treasury to "17 (*a*) P. W. Deposits" and challan enclosed.

*Abstract Notification dated the 12th June* 1940.

The attention of the public is drawn to the Notification calling for tenders for running a hotel in the compound of District Offices, Shimoga, published on page 1479, Part VI of the *Mysore Gazette*, dated 20th June 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on 28th of June 1940.

Earnest money required for the submission of the tender is Rs. 100 which should be credited to the Treasury to "17 (*a*) P. W. Deposits," and challan enclosed.

D. A. HUKERI,
*Executive Engineer.*

# MISCELLANEOUS DEPARTMENTS.

## OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

*Notice No. T. C. 295—37-38, dated 19th November* 1937.

**The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.**

F. A. HAMILTON,
*Inspector-General of Police.*